



कपुरकोट गाउँपालिका गाउँकार्यपालिकाको कार्यालय

कपुरकोट, सल्यान
कर्णाली प्रदेश, नेपाल

प.सं. २०८३/०८४

सं. २१

दरभाउपत्र पेश गर्ने सम्बन्धी सार्वजनिक सूचना ।

प्रथम पटक प्रकाशित मिति

२०८३/०६/२३

यस कपुरकोट गाउँपालिकाको आ. व . २०८३/०८४ को स्वीकृत वार्षिक योजना तथा कार्यक्रम अनुसार तपसिलको योजनामा निर्माण सम्बन्धी काम सार्वजनिक खरिद नियमावली, २०६४ को नियम ८५ (१) (क) बमोजिम खुला दरभाउपत्रको माध्यमबाट कार्यान्वयन गरिने भएकोले इच्छुक दरभाउपत्रदाता वा निर्माण व्यवसायीले रीतपूर्वकको दरभाउपत्र सिलबन्दी गरी मिति २०८३/०७/०९ गते सम्म गाउँपालिकाको कार्यालयमा पेश गर्नु हुन जानकारी गराइन्छ ।

तपसिल:

योजनाको नाम	योजना स्थल	लागत अनुमान रकम रु.	दरभाउ पत्र दस्तुर रु.	कैफियत
पन्द्र शैया अस्पतालको थप काम वडा नं. ३	वडा नं. ३ कपुरकोट, सल्यान	९,९९,७६०.८९	१०००.००	

आवश्यक कागजातहरू :

- १) प्यान / भ्याट दर्ता प्रमाणपत्र
- २) फर्म रजिष्ट्रेसन प्रमाणपत्र (नवीकरण आ.व. २०८३/०८४)
- ३) कर चुक्ता प्रमाणपत्र (आ.व. २०८२/०८३)
- ४) निर्माण व्यवसायी इजाजत प्रमाणपत्र
- ५) राजस्व तिरेको रसिद
- ६) प्रोप्राइटर बाहेकले दर्ता गर्ने भएमा अख्तियारनामाको सक्कल कागजात र नागरिकताको प्रतिलिपि
- ७) कार्यालयले जारी गरेको आधिकारिक दरभाउपत्रमा दर प्रविष्ट गरेको हुनुपर्ने

नोट : दरभाउ पत्र भर्ने फारम (BOQ) यसै साथ संलग्न गरिएको छ । सोहि फारममा दररेट पेश गरी सहिछाप लगाइ पेश गर्नुपर्ने छ । अन्यथा दरभाउपत्र ग्राह मानिने छैन ।

(सुन्दर कुमार थापा)


(सुन्दर कुमार थापा)

प्रमुख प्रशासकीय अधिकृत

Web: www.kapurkotmun.gov.np ✉ ito.kapurkotmun@gmail.com / kapurkotruralmun073@gmail.com

०८८-४९००६९/४९००७०

“कृषि पर्यटन र पर्वधार, कपुरकोट गाउँपालिकाको विकासको आधार”



योजनाको नाम: पूर्वाधार शाखामा ल्याब व्यवस्थापन तथा उपकरण खरिद
योजनाको ठेगाना: कपुरकोट गाउँपालिका, सल्यान

SN	Description of items	particulars	No.	unit	Bidder's Rate(NRS) in number	Bidder's Rate(NRS) in words	Amount Nrs.	Remarks
1	Supplying of cube mould	15 x 15 x 15 cm	6	nos				
2	Supplying of mortar mould	7 x 7 x 7 cm	6	nos				
3	Supplying of Laser Distance meter	0.05-100 m	1	set				
4	Supplying of Rebar RS350 Integrated Rebar Scanner		1	Set				
5	Transportation cost		1	LS				
Total								
Vat @13%								
Grand Total								

Name of Company:

Authorized Signature

Stamp of Company:

Date:

प्रमुख
प्रशासकीय अधिकृत


10	Providing & laying First class chimney made brick masonry work in superstructure with 1:4 cement sand mortar (1 cement : 4 sand) including lead upto 30 m with scaffolding, curing, cleaning & racking out mortar joint and making ducts, recesses where required all complete.	6.40	cum			
11	12.5 mm thick cement sand plaster work (1:4) including supply of materials, labor, mixing, levelling, curing & scaffolding etc. all complete as per drawing, specification and approval of engineer.	48.66	sqm			
12	Providing and applying two or more coats of washable distemper paint of approved manufacturer and shade over a coat of alkali resistant cement primer of approved manufacturer as per manufacturer's specifications to the surface of wall, ceiling, beams columns, canopies, staircase, lobbies etc., all complete as per drawings, specifications and instruction. The rates shall include for scraping, washing the surface with water, surface preparation, scaffolding etc., all complete as per the manufacturer's recommendations and as approved by the Engineer.	48.66	sqm			
15	Supplying and Fitting work of an X-ray Lead Door 5' x 7'	1.00	Nos			
16	Supplying and Fitting work of an X-ray Lead window 8" x 10"	1.00	Nos			
				Total		
				Vat @13%		
				Grand Total		

Name of Company:

Authorized Signature

Stamp of Company:

Date:


पञ्जाब प्रशासकीय अधिकारी




Kapurkot Rural Municipality
Office of Rural Municipal Executive
Kapurkot, Salyan
Karnali Province, Nepal
BILL OF QUANTITY(BOQ)

योजनाको नाम: पन्ध्र सैया अस्पताल थप काम वडा नं. ३
योजनाको ठेगाना: कपुरकोट गाउँपालिका वडा नं. ३, सल्यान

आ.व. २०८३-०८४

S.N	Description	Quantity	unit	Bidder's Rate(NRS) in number	Bidder's Rate(NRS) in words	Amount(Nrs.)	Remarks
1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved materials as drawings and technical specifications. @ Depth upto 3m (mechanical means)	66.788	cum				
2	Providing and laying of hand pack stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per drawing and technical specification. (Ref. Clause 1006 of SS DoR & S.N 10.8 of Norms DoR)	12.336	cum				
3	Providing and laying of PCC M:15 (Or 1:2:4 for nominal mix) in foundation complete as per drawing and technical specification.	7.71	cum				
4	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications, 60% M 15 concrete and 40% boulders/stones, using Mechanical Aid having upto lead 30 m lift 1.5m and including all forworks as per required.	21.94	cum				
5	Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing with cement mortar 1:2 as per Drawing and Technical Specifications., 600 mm internal dia.	22.50	m				


प्रकाश प्रसादीय अधिकृत